## Learning Estate Investment Programme (Phase 3) – Outcome-based Funding Criteria

Scottish Government (SG) funding will be available through the Outcomes Based Funding (OBF) model. SG funding will be released as the achievement of agreed outcomes is evidenced. The details of these outcomes are included in the table below:

Funded Outcome	Outcome to be achieved
1. Condition	Local authorities must provide evidence, through their annual returns that the facility is kept in condition A or B for a period of 25 years.
	This is intended to be a binary funding condition. In recognition of the potential for survey issues to be identified, removal of funding would be suspended for one year to allow for rectification of any issues leading to a C condition rating. The funding would be reinstated, the next financial year, once it could be demonstrated that the facility was in A/B condition again.
	If the building drops into condition C more than once during a five-year period, the condition funding element will be suspended without the one-year grace period, until the condition is rectified to A/B.
	In the event of exceptional circumstances such as fire or flood resulting in the condition of the building being unable to be rectified to an A/B condition within 1 year of becoming a C, or meaning that the facility drops into condition C for a second occasion, this will be reviewed on a case by case basis between the authority and SG.
2. Energy Efficiency	Authorities must provide evidence that the in-use energy target of 67/kWh/sqm/p.a. for core hours of 2,000 p.a. and core facilities is achieved.
	Core Facilities
	To provide consistency of definition across the variety of projects in the programme, the following facilities are excluded from
	the total energy consumption target:
	<ul> <li>Dedicated community/health facilities</li> </ul>
	<ul> <li>Swimming pool/hydrotherapy pool</li> </ul>
	External sports flood lighting

Production kitchens (serving multiple sites)
• Data centres (serving multiple sites)
Electric Vehicle Charging Points
Other (e.g. specialist vocational/industrial facilities, councils to propose)
Within the remaining core facilities, all energy uses relating to the building and users are included in the energy target. The target includes all consumed energy regardless of source e.g. energy provided from renewable sources is included in the same manner as gas or electricity from the mains or grid. Contribution from heat pumps should be included on the output side rather than input side to support the aim of creating energy efficient buildings using a fabric first approach.
Core Hours
To recognise that councils and individual schools have different operational hours and term dates, the target is anticipated to cover all energy uses during a bank of 2000 operational hours per annum. If the facilities are operational for more or less hours then a pro rata approach should be taken to compare against the target.
Building use purely for cleaning, maintenance or security tasks will not be considered as operational hours.
Example
To report on previous year:
<ul> <li>total open operational hours of a facility for school and community use (excluding cleaning etc) = 3000 hours</li> </ul>
<ul> <li>total annual energy consumption from all sources (after exclusions) = 120 kWh/m2/annum</li> </ul>
<ul> <li>reportable core energy consumption would be (2000/3000) x 120 = 80 kWh/m2/annum</li> </ul>
Energy Outcome Funding
This is recognised as being an ambitious target, therefore it is not anticipated that this will be a pass/fail outcome for
funding but that a sliding scale will be attached.
From feedback and discussion with Directors of Finance, ADES Resources and SHOPs the sliding scale is grouped into ranges with a corresponding alteration to funding depending on which range is demonstrated as being achieved:

Energ kWh/
A 67
B 84
C 100
D 110
E 131
If the fa The fun energy this willFollowin 

	If the cost of providing t is not physically possible solution.		•	, ,		-	
4. Economic Growth	Investment in infrastruc published benchmarks c			-		•	•
	The authority will requir benchmarks published J construction contract va	uly 2017. The r	•	•		• •	
	£1-3.5m	£3.6-6m	£6.1-10m	£10.1m-15m	£15.1-20m	£20.1-30m	£30.1-40m
	1	4	5	10	11	12	14
	£40.1-50m	£50.1-60m	£60.1-70m	£70.1-80m	£80.1-90m	£90.1-100m	
	15	18	19	19	21	22	
	Funding will be available accordingly. E.g. if 12 jobs is the targ be available. This outcome could be r engagement is embedde It is proposed that becau project that the funding year period.	et but only 11 a nulti-faceted a ed in the design use the achieve	are evidenced a nd also provide n and construct ement of this o	as being achieve e a measure to e tion process thre utcome will hap	ed then 11/12t ensure training ough site visits open in the des	hs of the fundin places are supp and work expe ign and constru	g for that outcome wil ported and learner rience placements. ction phase of the
5. Construction Embodie		bon is key to e	ensuring the lor	ng-term sustaina	ability of the le	arning estate. B	uilding on the
Carbon	Operational Energy Targ	•				•	
	Embodied Carbon footp Construction Embodied	•		design and cons	truction to pra	ctical completio	n.
	Construction Embodied	Carbon Outco	me				

Local authorities should evidence that the construction embodied carbon target of 600 kgCO2e/m2 for core facilities is
achieved. Local authorities should track and record this throughout the project stages using an assessment tool compliant with BRE IMPACT methodology managed by an assessor with appropriate expertise.
Evidence of achieving this target using actual material, product, transport and contractor activity data will be required at project completion.
Methodology
The Construction Embodied Carbon target should be assessed for the building and external plant only, excluding external
works and loose FF+E. This should include Stages A1-A5 "from cradle to practical completion" as defined in the RICS Professional Statement of Whole Life Carbon:
- A1-A3: Products/Materials (c. 95% of target CO2 emissions)
- A4: Transport of materials and products to site
- A5: Construction site operations
Local Authorities should consider the guidance in the Net Zero Public Sector Building Standard (NZPSBS) Objective 2.
Core Facilities
To provide consistency of definition across the variety of projects in the programme, the Construction Embodied Carbon
target should only include the core facilities, as defined in Outcome 2 – Energy Efficiency.
Construction Embodied Carbon Outcome Funding
This is recognised as being an ambitious target, therefore it is not anticipated that this will be a pass/fail outcome for
funding but that a sliding scale will be attached.
The construction embodied target funding is grouped into bands corresponding alteration to funding depending on which range is demonstrated as being achieved:
ומווצב וז עבוווטווזנו מנבע מז גבוווצ מנווופעבע.

A <600       100%         B 601-666       90%         C 667-733       60%         D 734-800       30%
C 667-733 60%
D 734-800 30%
E 800+ 0%

If the facility exceeds 800 kgCO2e/m2 of construction embodied carbon, no funding will be available for that outcome.

## Refurbishment

The Construction Embodied Carbon funding targets will apply to all projects in the programme – Newbuilds, Refurbishments and Extensions. Where a proposed project has over 50% GIFA as refurbishment it will automatically be deemed Band A compliant and receive 100% associated Construction Embodied Carbon funding. A Construction Embodied Carbon assessment should be provided for all projects.