



Legend

Planting/Soft Landscaping

- Woodland Edge Mix**
w. Woodland understorey planting
- Woodland Edge Mix**
- Coniferous Woodland Mix**
w. Meadowland Mix 2
- Wetland Fringe: 10,098m²**
- Meadowland Mix 1**
- Meadowland Mix 2**
- SUDs**
- Re-aligned Burn corridor**



Woodland Edge Mix

WE1	WE2	WE3	WE4	WE5	% Mix	Code	Species	Height (cm)	Grown	Transplant	Height grade	Density
1274	258	383	223	261	15	Ac	Acer campestre	175-200	B	2x	Feathered	1no/m ²
1274	258	383	223	261	15	Ag	Alnus glutinosa	175-200	B	2x	Feathered	1no/m ²
1274	258	383	223	261	15	Cm	Crataegus monogyna	125-150	B	2x	Feathered	1no/m ²
1274	258	383	223	261	15	Pa	Prunus avium	150-175	B	2x	Feathered	1no/m ²
1274	258	383	223	261	15	Qr	Quercus robur	150-175	B	2x	Feathered	1no/m ²
1274	258	383	223	261	15	Sv	Salix viminalis	200-250	B	2x	Feathered	1no/m ²
848	174	254	149	173	10	Sa	Sorbus aucuparia	200-250	B	2x	Feathered	1no/m ²

Coniferous Woodland Mix

CW1	CW2	% Mix	Code	Species	Height (cm)	Grown	Transplant	Height grade	Density
1539	781	25	Ag	Alnus glutinosa	175-200	B	2x	Feathered	1no/m ²
1539	781	25	Jc	Juniperus communis	100-125	RB	3x	Feathered	1no/m ²
1539	781	25	Ps	Pinus sylvestre	150-175	RB	4x	Feathered	1no/m ²
1539	781	25	Sa	Sorbus aucuparia	200-250	B	2x	Feathered	1no/m ²

Woodland Understorey Planting

WUP1	WUP2	% Mix	Code	Species	Size (cm)	Grown	Habits/breaks	Density
2680	1860	35	Ca	Cornus alba 'Sibirica'	40-60	2L	Branched	3no/m ²
2680	1860	35	Cc	Cornus canadensis	15-20	2L	Bushy	3no/m ²
2297	1595	30	Rc	Rosa carina	40-50	2L	Branched	3no/m ²

Wetland Fringe

WF1	WF2	WF3	% Mix	Code	Species	Size (cm)	Grown	Habits/breaks	Density
1025	1981	5450	20	Cp	Caltha palustris	20-30	1L	Clump forming	5no/m ²
1025	1981	5450	20	Ip	Iris pseudocarus	20-30	1L	Suckering	5no/m ²
1025	1981	5450	20	Ln	Lysimicha nummularia	20-30	1L	Matforming	5no/m ²
1025	1981	5450	20	Ma	Mentha aquatica	20-30	1L	Matforming	5no/m ²
1025	1981	5450	20	Ms	Myosotis scorpioides	20-30	1L	Clump forming	5no/m ²

Meadowland Mix 1
Mavisbank Mix by Scotia Seeds (www.scotiaseeds.co.uk), sown at a rate of 3g/m²

Meadowland Mix 2
Woodland Meadow Mix by Scotia Seeds (www.scotiaseeds.co.uk), sown at a rate of 3g/m²

Notes: Planting Method
Thoroughly cultivate all areas to be planted to a minimum depth of at least 300mm. Include during the cultivation mulching compost at a rate of 15 litres per m².

All trees / shrubs to be planted in groups of 5 - 9 of the same species, each species evenly distributed throughout the planting area. Each plant is to be planted in pits of 300mm diameter and depth, backfilled with imported topsoil to BS3882, incorporating 5 litres of peat free compost into each pit.

Following the completion of planting, apply a 50mm layer of well rotted bark chippings.
Mesh fencing to be provided around all planting areas to protect establishing trees and shrubs from livestock and rabbits.

Rev.	Date	Reason
D	09.12.22	Wetland Fringe amended as per clients comments, planting nos amended for wetland fringe and Woodland Edge (WE1, WE4, WE5)
C	18.11.22	Remove hedgerow
B	07.11.22	Added planting plan
A	01.09.22	Amend planting to RLB

Project	Portgordon Proposed Warehousing
----------------	------------------------------------

Title	Landscape Planting Plan
--------------	-------------------------

Date	Scale	Drawn	Checked
12.08.22	1:2000 @ A2	KB	GS

Job	Suitability	No.	Issue	Revision
2095	S3	L02	Planning	D

LI WORKSTAGE:	0/1	2	3	4	5	6
	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

DISCLAIMER:
Do not scale from this drawing.
All dimensions to be verified on site prior to commencement of works.
Drawing to be read in conjunction with related TGP drawings, consultants drawings and any other relevant information.
This drawing is the copyright of TGP Landscape Architects Ltd. unless otherwise specified.